## SUPER CORFLO >>>>

## **"SOIL BOX" PIPE STIFFNESS TESTING**

"SOIL BOX" PIPE STIFFNESS	
SUMMARY	

	5% Deflection	10% Deflection	
DB120	19,310	DNR	
HDPE	13,098	12,019	
SCH 40	14,975	DNR	
* Test Conducted by 3rd party in October 2019 * Test results in psi			

P (905) 396-5964

E info@cdfutilitysupply.ca



For more info contact your CDF Sales Rep CDFUtilitySupply.ca

Pg 1 of 2

## SUPER CORFLO >>>>

## **"SOIL BOX" PIPE STIFFNESS TESTING**

	TESTING, RESEARCH, CONSULTING AND FIELD SERVICES Austin, TX - USA   Anaheim, CA - USA   Anderson, SC - USA   Gold Coast - Australia   Suzhou - China
10/28/2019	
Mail To:	Bill To:
Tim Shaw Project Engineer OEM/Miller Division of Ilpea Office: 330-995-2 Cell: 330-285-392 Email: tshaw@ilp	Industries 475
Dear Mr. Shaw ,	
	ng TRI for your Pipe testing needs. present this final report for chamber testing per ASTM D2412
TRI Job Number:	50637
Material Tested:	4" Diameter Pipes: PVC - DB120 Gray Pipe PVC Schedule 40 HDPE Dual Wall
Tests Requested:	Modified ASTM D2412 Pipe Stiffness Test at 5% Deflection
Results:	The results are shown on the following page.
	uestions of require any additional information, please call us at 1-800-880-8378
Sincerely, Mario Paredes Project Manager TRI-Environmenta	al
	9063 Bee Caves Road / Austin, Texas 78733 / ph: 512 263 2101 / fax: 512 263 2558 / www.GeosyntheticTesting.com



P (905) 396-5964
E info@cdfutilitysupply.ca

For more info contact your CDF Sales Rep CDFUtilitySupply.ca

Pg 2 of 2